No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
20	Flooring with cement concrete (1 : 2 : 4) $1\frac{1}{2}''$ thick over a bed of 4" thick lime concrete with topping of $\frac{1}{2}''$ thick red ochre and lines cut nicely to design of tiles	Sqr.	18 0 0	17·08	
21	Flooring with burnt stone slabs 3" thick over a bed of 3" thick surki concrete and pointing the surface with cement and lined nicely	„	20 0 0	0·60	
22	Wrought iron railing as per design to be furnished during construction, 3' high between pillars of front verandah	R.ft.	2 8 0	20	
23	Teak wood doors of well seasoned Mysore teak, 3"×5" frames, $1\frac{1}{2}''$ thick shutters $\frac{1}{3}$ panelled at bottom and $\frac{2}{3}$ glazed at top without bottom sills with $\frac{1}{8}''$ thick glass of variety to be specified with required type of ventilators complete with Acme brass or copper oxidized fittings such as rim locks with handles, hinges, hooks, barrel tower bolts of suitable size, etc., including tarring the sides for the seat in brick work with 2 coats of approved Dulux or Jhonson & Nickelson or any kind of water proof varnish, etc., complete as per specification ...	S.ft.	1 6 0	294	
24	Teak wood windows of well seasoned Mysore teak, with frames 3"×4" having fully glazed shutters 1" thick, with louvred shutters for the ventilators fixed to them including usual iron fittings (to be furnished during construction) $\frac{3}{4}''$ dia. iron bars placed $4\frac{1}{2}''$ to 5" C to C with 2 coats of varnish for inner windows and 2 coats of paint for outer ones (to be furnished during construction) etc., complete	„	1 8 0	180	
25	Teak wood ventilators 3"×4" with glazed shutter 1" thick with usual fittings and 2 coats of required painting (design will be furnished during construction)	„	1 2 0	45	
26	R.C.C. perforated ventilators $1\frac{1}{2}''$ to 2" thick by 2" frame all round with necessary reinforcements (design to be furnished during execution) ..	„	0 12 0	9	
27	Rain water down pipes of cast iron 3" square with bends, etc., complete..	R.ft.	1 4 0	26	
28	Smoke chimney in kitchen as per design to be furnished during execution	Each	20 0 0	1	

M. K. RAJAM IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE *EX-OFFICIO* CONTROLLER OF PATENTS AND DESIGNS IN MYSORE, BANGALORE.

No. C2. Pat. 199—38-39, *dated* 16*th November* 1939.

NOTICE OF ACCEPTANCE OF APPLICATION FOR PATENT

No. 199 *of* 1938-39, *dated* 18*th April* 1939.

Notice is hereby given that all persons interested in opposing the grant of a patent on the application referred to below may at any time within three months of the date of this notification give notice to the *Ex-officio* Controller of Patents and Designs in Mysore, in the prescribed Form No. 5 of such opposition.

Les Usines De Melle of France.

"Improvements in or relating to the extraction of Glycerine from Glycerine containing Liquids."

Any one desiring to inspect copy of the specification of the above may call at the Office of the *Ex-officio* Controller of Patents and Designs on any working day between 11 A.M. and 5 P.M. A sum of rupee one will be charged for such inspection.

L. MUNISWAMY,
For Ex-officio *Controller of Patents and Designs.*

Printed by the Superintendent at the Government Press, Bangalore, 1939.